



CLAY COUNTY SHERIFF'S OFFICE
SHERIFF DARRYL DANIELS
P.O. BOX 548
(904) 264-6512 or (352) 473-7211
FAX (904) 284-0710
GREEN COVE SPRINGS, FLORIDA 32043-0548

ADDENDUM 1

Request for Proposal (RFP) #: B19-003

**Project Name: CCSO A/V Equipment for 3rd Floor Conference Room
(JAG Funded)**

February 7, 2019

Question 1

Task 1 - May an 86" LED substitute for the 86" LCD specification? Any specific requirements other than "support viewers up to approximately 19' from screen"?

The CCSO will accept an LED substitute.

Question 2:

Task 2 and 3 have the same function and comprise the same ports. Do you require Task 2 components in addition to Task 3? The Crestron DM-TX-200-C-2G-W-T encompasses USB, HDMI, VGA and Audio. Task 3 States it will be co-located with Task 2.

One wall plate that contains one HDMI port one VGA port and two USB ports can substitute for the one plate with HDMI and VGA and another plate with two usb. There are two locations where these inputs will be required.

Question 3

Is it acceptable for Task 4 - Crestron AM-200 and Task 1 - Crestron DMPS3-4K-350-C to be combined as a single Sku : Crestron - DMPS3-4K-350-C-AIRMEDIA?

Yes, provided the same functionality, ie AM license included and the same AM version features as included with the AM200.

ADDENDUM 1
February 7, 2019

Question 4

Task 13 - What are the requirements of the "Press Feed Wall Plate"? What connections does the plate need to have?

The Press Feed Wall Plate is a direct connection to the audio output of the system.

In response to questions posed during the non-mandatory walk through conducted on February 7, 2019, the CCSO offers the following clarifications:

Clarification to Task 2 of 5.03.1.

The vendor will be responsible for removing the existing LCDs. The removed LCDs will be placed in storage.

Clarification to Tasks 2 & 3 of 5.03.2

The existing column is a concrete pillar with an existing gap between the drywall. No back boxes are present.

Clarification to Tasks 9 of 5.03.2

Mic will be a desk stand on the podium.

Clarification to Tasks 11 of 5.03.2

The audio feed from the video switching system should be able to be sent to the outputs detailed in this RFP.

Clarification to Tasks 12 of 5.03.2

The room is approximately 50' x 30'.
All (12) speakers will be placed in the conference room.
The room has a drop ceiling. The drop is approximately 4'.

ADDENDUM 1
February 7, 2019

Clarification to Tasks 13 of 5.03.2

The press feed will be analog audio.

Clarification to Tasks 14 of 5.03.2

The CCSO will provide data connectivity to the location of the TSP. The contractor will be responsible for pulling all wires.

The CCSO prefers a 10”.

Clarification to Tasks 15 of 5.03.2

The location of the storage room has a/c but no return.

The CCSO prefers a rack on wheels as opposed to a fixed mounted rack.

As the rack is located in a locked storage room, the rack does not require a door, ventilation or locking mechanism.

Task 1 and 2 of Section 5.03.3 is hereby deleted and shall read as:

1. Provide and install two (2) Pan/Tilt/Zoom (PTZ) cameras in the drop ceiling.
2. The cameras will be connected to the OFE PC via a USB connection to the DSP.